ONE EXEMPTION DOES NOT EXCLUDE OTHER REGULATORY REQUIREMEMNTS

0<1 Acre

Land Disturbance 1 Acre or greater

E&S
BMPs required
Sites < 0.75 acres

SJA/DPW recommends sites that are 0.75 acres submit NOI due to potentially overstepping footprints

State Regulatory Requirement NOI MUST be submitted

Contractor submits E&SPCP to NRCS for Review/Approval of E&SPCP & "Technical Oversight"

Contractor submits NRCS Approved E&SPCP & NRCS Approval Form with NOI packet to DPW Environmental Division

NOI packet routed to DPW for Signature; Then returned to DPW Env. Division

NOI submitted to GA EPD via Certified Mail by DPW Env. Division

Timber Harvest may commence 14 Calendar Days from certified mailing date of NOI Packet to GA EPD; utilizing GA Forestry BMPs.
Once timber harvest is complete; grubbing/grading may commence once E&SPCP BMPs have been implemented.

Complete process Approximately 19-21 days; NOTE not inclusive of Stream Buffer Variance add an additional 90-120 days